

**NAME OF WORK : CONSTRUCTION OF HIGH LEVEL MAJOR BRIDGE ON PATI CHOGATH  
ROAD TA VALLABHIPUR DIST BHAVNAGAR**

**BILL OF QUANTITIES**  
**Percentage Rate Tender (Up to INR 50 Cr.)**

| Item No. | Description of Item                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | Quantity | Unit   | Estimated Rates | Amount    |
|----------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|--------|-----------------|-----------|
|          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |          |        | Rate In figures |           |
| 1        | 2                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | 3        | 4      | 5               | 6         |
| 1        | Dismantling of Structures (Mechanical Means)<br>Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead of 1000 m as per Technical Specification Clause 202.                                                | 268.20   | Cu.m.  | 886.05          | 237639.36 |
| 2        | Clearing and Grubbing Road Land (By Mechanical Means)<br>Clearing and grubbing road land including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300 mm, removal of stumps of such trees cut earlier and disposal of unserviceable materials and stacking of serviceable material to be used or auctioned, upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150 mm in thickness as per Technical Specification Clause 201. | 2.55     | Hectre | 28393.04        | 72402.25  |

| Item No. | Description of Item                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | Quantity | Unit  | Estimated Rates | Amount     |
|----------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|-------|-----------------|------------|
|          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |          |       | Rate In figures |            |
| 1        | 2                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | 3        | 4     | 5               | 6          |
| 3        | Marking out the centre line of the bridge & various other component structure & complete lining out and levelling with the theodolites, levels including constructing necessary masonry reference pillars for lines and levels and establishing necessary bench marks etc. complete as directed including the cost of all materials & labour charges etc. complete.                                                                                                                                                                                                                                                                                                                                                | 1.00     | Each  | 30300.00        | 30300.00   |
| 4        | Diversion of water course, providing cofferdam and bund or island as may be necessary for foundation and maintaining the same for the period as may be necessary. (A) Diversion by Channel (F) Abutment Left (including returns/ wing walls) Preparing Earthen Bund with earthwork for embankment including breaking clods, dressing with all lead and lift and including watering rolling and consolidation of subgrade in layer sat O.M.C. to required dry density including filling thede pression which occurduring the processusing power roller 8T to 10T. (E) From Borrow area within 3.0KM. lead for construction period after finishing of work site to be cleared by as directed by Engineer in Charge . | 1260.00  | Cum   | 169.44          | 213491.38  |
| 5        | Providing flood gauge marks on substructure as per design including painting complete.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | 67.30    | R.mt. | 148.89          | 10020.58   |
| 6        | Providing and laying filter media 600mm thick as directed at the back of abutments, returns and retaining wall as per detailed specifications.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | 2341.00  | Sq.m. | 1180.34         | 2763167.75 |

| Item No. | Description of Item                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | Quantity | Unit  | Estimated Rates | Amount     |
|----------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|-------|-----------------|------------|
|          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |          |       | Rate In figures |            |
| 1        | 2                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | 3        | 4     | 5               | 6          |
| 7        | Providing & laying Weep holes in RCC abutment, Return wall and retaining wall with 100 mm dia PVC pipe and non-corrodible grating and geotextile, extending through the full width of the structure with slope of 1V:20H etc. complete as per drawing and technical specification.                                                                                                                                                                                                              | 2341.00  | Each  | 58.54           | 137041.20  |
| 8        | Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 Sandy Material                                                                                                                                                                                                                                                                                                                                                        | 6348.76  | Cu.m. | 538.85          | 3420998.22 |
| 9        | Excavation for foundation in sand, gravel, clay soft soils and murrum etc. including shoring, strutting dewatering as necessary and disposing of the excavated stuff as directed.(A) Depth upto 3.0 M. and lead upto 100m for 10 Cum                                                                                                                                                                                                                                                            | 3850.00  | Cu.m. | 486.77          | 1874062.58 |
| 10       | Excavation for foundation in sand, gravel, clay soft soils and murrum etc. including shoring, strutting dewatering as necessary and disposing of the excavated stuff as directed.(B) Depth from 3.0 to 6.0 M. and lead upto 100m for 10 Cum                                                                                                                                                                                                                                                     | 27.00    | Cu.m. | 571.08          | 15419.28   |
| 11       | Providing and laying in positions machine mixed Plain controlled Cement Concrete M15 grade for leveling course below foundation, approach slab , etc. at other places as directed by Engineer-in-charge with graded broken stone aggregate from 6mm to 40 mm including tamping, vibrating, leveling and curing complete with all formwork, dewatering wherever required including all materials, labours, plants, machineries & tools, all leads and lifts, etc. complete as per specification. | 169.50   | Cu.m. | 3910.10         | 662762.61  |

| Item No. | Description of Item                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | Quantity | Unit  | Estimated Rates | Amount     |
|----------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|-------|-----------------|------------|
|          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |          |       | Rate In figures |            |
| 1        | 2                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | 3        | 4     | 5               | 6          |
| 12       | Providing and cast in situ controlled cement concrete of M-35 grade as per relevent code for reinforced cement concrete with 20mm down graded crushed stone aggregates of required size in foundation of pier abutment For Pile Cap etc. & Sub-structure including form work shuttering and supporting arrangement (excluding cost of reinforcement ) and transporting concrete from batching plant by transit mixture, placing it in position, Compacting with needle Vibrator including Curing with all labour, material, machinery, all lead, lift etc complete as per drawing and Technical specification.                                                                                                                                                                                                                                                                                                                       | 554.00   | Cu.m. | 5118.68         | 2835748.72 |
| 13       | <p>Providing and placing the reinforcement in designed position, fixing, lowering in position TMT bars Fe-550D grade conforming to IS 1786 for foundation of pier &amp; abutment For Pile Cap etc at all levels. The rates includes for supply, loading, unloading, transporting to site, cutting, bending, hooking, placing, tying in position with contractor's own black annealed binding wire, welding, etc. Welding and supporting in position to ensure lines and levels during concreting, maintaining proper cover / spacing, all leads &amp; lifts,etc. including contractor's own equipment, labour, supervisor, taxes, machineries, etc. complete as per drawings and specification.</p> <p>1) The waste cut pieces and laps shall not be included in the paying quantity.<br/> 2) Black annealed binding wire shall not be included in the paying quantity.<br/> 3) The work shall be done as per execution drawing.</p> | 112.09   | MT    | 73217.53        | 8206952.49 |

| Item No. | Description of Item                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | Quantity | Unit  | Estimated Rates | Amount     |
|----------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|-------|-----------------|------------|
|          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |          |       | Rate In figures |            |
| 1        | 2                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | 3        | 4     | 5               | 6          |
| 14       | Empty boring through all sorts of strata for providing 1.20 m dia RCC bored piles to required depth including flushing necessary casting pipe with all plants and equipments as required as per detailed specifications for Abutment and Piers (Excluding Concrete & Reinforcement)                                                                                                                                                                                                                | 590.00   | R.mt. | 3833.71         | 2261887.43 |
| 15       | Carrying out load test on any pile as per standard procedure laid down in the IS:2911 specification including construction of test cap, dismantling the cap after test and cleaning the site and maintaining complete records of load settlement as directed by Engineer and as per specification, and submission of records.<br>a. Load testing of foundation piles including loading with necessary kentledge of any other suitable method as per details (Initial load Test)<br>1200mm dia Pile | 3.00     | Each  | 327745.00       | 983235.00  |
| 16       | Carrying out load test on any pile as per standard procedure laid down in the IS:2911 specification including construction of test cap, dismantling the cap after test and cleaning the site and maintaining complete records of load settlement as directed by Engineer and as per specification, and submission of records.<br>b. Load testing of foundation piles including loading with necessary kentledge of any other suitable method as per details (Routine load Test)<br>1200mm dia Pile | 3.00     | Each  | 256237.00       | 768711.00  |

| Item No. | Description of Item                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | Quantity | Unit  | Estimated Rates | Amount     |
|----------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|-------|-----------------|------------|
|          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |          |       | Rate In figures |            |
| 1        | 2                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | 3        | 4     | 5               | 6          |
| 17       | Performing Integrity Test (low strain) on vertical pile. The item shall include chipping of weak concrete at the top of pile, leveling, bending of reinforcing bars, preparation of pile head including testing with pile driving analyser or approved equivalent. To be carried out at least 15 days after concreting of piles. A specialist approved Agency shall be employed by the Contractor for the test. The test shall be carried out as per relevant ASTM code. The item is including complete testing with approved apparatus, analysis of results and conclusions including submission of test reports in three hard copies with soft copy in CD.<br>1200mm dia Pile | 42.00    | Each  | 893.85          | 37541.70   |
| 18       | Providing and casting in situ controlled cement concrete M-35 for RCC bored pile from 1.2 m. dia. using Tremie Pipe including necessary flushing, dewatering, formwork, mixing in mechanised batch mix plant, transporting, compacting, and finishing including all leads & lifts complete as per detailed specifications. (Excluding Reinforcement)                                                                                                                                                                                                                                                                                                                            | 724.00   | Cu.m. | 4919.71         | 3561870.04 |
| 19       | Chipping and dressing of the RCC piles upto cut-off level (Min. 1 D) including cleaning of reinforcement and removal of dismantled materials, etc. for providing pile caps as directed by Engineer and as per specification. for 1200 mm dia. pile.                                                                                                                                                                                                                                                                                                                                                                                                                             | 57.00    | Cu.m. | 886.05          | 50505.01   |
| 20       | Providing and installing 6 mm MS liner for bored-cast-in-situ concrete piles including applying protective coating as per drawing and specification and as directed by Engineer.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | 38.00    | MT    | 47323.73        | 1798301.81 |

| Item No. | Description of Item                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | Quantity | Unit | Estimated Rates | Amount      |
|----------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|------|-----------------|-------------|
|          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |          |      | Rate In figures |             |
| 1        | 2                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | 3        | 4    | 5               | 6           |
| 21       | <p>Providing and placing the reinforcement in designed position, fixing, lowering in position TMT bars Fe-550D grade conforming to IS 1786 for Pile etc at all levels. The rates includes for supply, loading, unloading, transporting to site, cutting, bending, hooking, placing, tying in position with contractor's own black annealed binding wire, welding, etc. Welding and supporting in position to ensure lines and levels during concreting, maintaining proper cover / spacing, all leads &amp; lifts,etc. including contractor's own equipment, labour, supervisor, taxes, machineries, etc. complete as per drawings and specification.</p> <p>1) The waste cut pieces and laps shall not be included in the paying quantity.<br/> 2) Black annealed binding wire shall not be included in the paying quantity.<br/> 3) The work shall be done as per execution drawing.</p> | 145.85   | MT   | 73217.53        | 10678776.17 |

| Item No. | Description of Item                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | Quantity | Unit  | Estimated Rates | Amount     |
|----------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|-------|-----------------|------------|
|          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |          |       | Rate In figures |            |
| 1        | 2                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | 3        | 4     | 5               | 6          |
| 22       | <p>Providing and casting in-situ Reinforced Cement Concrete M30 grade controlled cement concrete in pier, abutment &amp; return wall etc. using 6mm to 20mm machine crushed well graded stone aggregate, sand of approved quality, OPC53 grade cement with contractor's own concrete mix design as approved by PWD, etc. complete. The rate is inclusive of all materials, including necessary mixing in fully automatic batch mix plant, transporting concrete by pontoon or tug boats etc, curing,dewatering, vibrating, placing in position, scaffolding, staging, shuttering, formworks, deshuttering carefully, making good the damages,fixing embedment, inserts, pockets, wherever necessary, with all lead and lift with contractor's labour,tools &amp; plants, machineries, as required,</p> <p>with F3 type exposed concrete finish and form mark.Any honeycombing / Undulation found shall be rectified to match F3 class finish. Note:- Rates in items shall include cost of providing grooves, chamfers, moulding, cut-out etc. in formwork. The work will include placing in position of necessary fixtures, sleeves for various purposes, etc. complete as per drawings, specifications and as directed by the Engineer in charge. The rate shall also include preparation of construction joints as per specifications and provide approved wire mesh/weld mesh at such location as approved by the Engineer-in-charge or as shown in drawings.</p> <p>For Height 0 .00 to 5.00m</p> | 826.80   | Cu.m. | 5342.90         | 4417509.72 |

| Item No. | Description of Item                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | Quantity | Unit  | Estimated Rates | Amount     |
|----------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|-------|-----------------|------------|
|          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |          |       | Rate In figures |            |
| 1        | 2                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | 3        | 4     | 5               | 6          |
| 23       | <p>Providing and casting in-situ Reinforced Cement Concrete M30 grade controlled cement concrete in pier, abutment, return wall &amp; Retaining Wall etc. using 6mm to 20mm machine crushed well graded stone aggregate, sand of approved quality cement with contractor's own concrete mix design as approved by PWD, etc. complete. The rate is inclusive of all materials, including necessary mixing in fully automatic batch mix plant, transporting concrete by pontoon or tug boats etc, curing,dewatering, vibrating, placing in position, scaffolding, staging, shuttering, formworks, deshuttering carefully, making good the damages,fixing embedment, inserts, pockets, wherever necessary, with all lead and lift with contractor's labour,tools &amp; plants, machineries, as required,</p> <p>with F3 type exposed concrete finish and form mark.Any honeycombing / Undulation found shall be rectified to match F3 class finish. Note:- Rates in items shall include cost of providing grooves, chamfers, moulding, cut-out etc. in formwork. The work will include placing in position of necessary fixtures, sleeves for various purposes, etc. complete as per drawings, specifications and as directed by the Engineer in charge. The rate shall also include preparation of construction joints as per specifications and provide approved wire mesh/weld mesh at such location as approved by the Engineer-in-charge or as shown in drawings.</p> <p>Height 5.00 to 10.00m</p> | 380.00   | Cu.m. | 5660.04         | 2150815.20 |

| Item No. | Description of Item                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | Quantity | Unit  | Estimated Rates | Amount    |
|----------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|-------|-----------------|-----------|
|          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |          |       | Rate In figures |           |
| 1        | 2                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | 3        | 4     | 5               | 6         |
| 24       | <p>Providing and casting in-situ Reinforced Cement Concrete M30 grade controlled cement concrete in piercap, abutment cap, dirt wall, Pedestal &amp; seismic arrester etc. including controlled cement concrete M-35 bed blocks or pedestals of required size below bearings as per detailed drawings, centering, shuttering, scaffolding, wherever necessary, laying vibrating, curing and finishing complete. using 6mm to 20mm machine crushed well graded stone aggregate, sand of approved quality, OPC53 grade cement with contractor's own concrete mix design as approved by client, etc. complete. The rate is inclusive of all materials, including necessary mixing in fully automatic batch mix plant, transport, curing, vibrating, placing in position, scaffolding, staging, shuttering, formworks,</p> <p>desluttering carefully, making good the damages, fixing embedment, inserts, pockets, wherever necessary, with all lead and lift with contractor's labour, tools &amp; plants, machineries, as required, with F3 type exposed concrete finish and form mark. Any honeycombing / Undulation found shall be rectify to match F3 class finish.</p> <p>Note:- Rates in items shall include cost of providing grooves, chamfers, moulding, cut-out etc. in formwork. The work will include placing in position of necessary fixtures, sleeves for various purposes, etc. complete as per drawings, specifications and as directed by the Engineer in charge. The rate shall also include preparation of construction joints as per specifications and provide approved wire mesh/weld mesh at such location as approved by the Engineer-in-charge or as shown in drawings</p> | 130.00   | Cu.m. | 5422.69         | 704949.70 |

| Item No. | Description of Item                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | Quantity | Unit | Estimated Rates | Amount     |
|----------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|------|-----------------|------------|
|          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |          |      | Rate In figures |            |
| 1        | 2                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | 3        | 4    | 5               | 6          |
| 25       | <p>Providing and placing the reinforcement in designed position, fixing, erecting or lowering in position TMT bars Fe-550D grade conforming to IS1786 for pier, abutment &amp; return wall etc all categories &amp; depth, at all levels. The rates includes for supply, loading, unloading, transporting to site, cutting, bending, hooking, placing, tying in position with contractor's own black annealed binding wire, welding, etc. Welding and supporting inposition to ensure line sand levels during concreting, maintaining proper cover / spacing, all leads &amp; lifts, etc. including contractor's own equipment, labour, supervisor, taxes, machineries, etc. complete as per drawings and specification.</p> <p>1) The waste cut pieces and laps shall not be included in the paying quantity.<br/> 2) Black annealed binding wire shall not be included in the paying quantity.<br/> 3) The work shall be done as per execution drawing.</p> | 135.12   | MT   | 73217.53        | 9893152.11 |
| 26       | <p>Providing and placing the reinforcement in designed position, fixing, erecting or lowering in position TMT bars Fe-550D grade conforming to IS1786 for piercap,abutment cap,pedestal,sesmic arrester &amp; dirtwall etc all categories &amp; depth, at all levels. The rates includes for supply, loading, unloading, transporting to site, cutting, bending, hooking, placing, tying in position with contractor's own black annealed binding wire, welding, etc. Welding and supporting inposition to ensure line sand levels during concreting, maintaining proper cover / spacing, all leads &amp; lifts, etc. including contractor's own equipment, labour, supervisor, taxes, machineries, etc. complete as per drawings and specification.</p>                                                                                                                                                                                                      | 16.00    | MT   | 73217.53        | 1171480.42 |

| Item No.  | Description of Item                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | Quantity      | Unit         | Estimated Rates | Amount            |
|-----------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------|--------------|-----------------|-------------------|
|           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |               |              | Rate In figures |                   |
| <b>1</b>  | <b>2</b><br>1) The waste cut pieces and laps shall not be included in the paying quantity.<br>2) Black annealed binding wire shall not be included in the paying quantity.<br>3) The work shall be done as per execution drawing.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | <b>3</b>      | <b>4</b>     | <b>5</b>        | <b>6</b>          |
|           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |               |              |                 |                   |
| <b>27</b> | Providing and casting in-situ Reinforced Cement Concrete M30 grade controlled cement concrete in Solid Slab using 6 mm to 20 mm machine crushed well graded stone aggregate, sand of approved quality, OPC 53 grade cement with contractor's own concrete mix design as approved by client ,etc.complete as per specification.<br>The rate is inclusive of all materials, including necessary mixing in fully automatic batch mix plant, transport, curing, vibrating, placing in position, scaffolding, staging, shuttering, formworks, deshuttering carefully, making good the damages, fixing embedment, inserts, pockets,<br><br>wherever necessary, with all lead and lift with contractor's labour, tools & plants, machineries, as required, with F3 type exposed concrete finish and form mark. Any honeycombing / Undulation found shall be rectify to match F3 class finish. | <b>608.00</b> | <b>Cu.m.</b> | 5481.27         | <b>3332612.16</b> |
| <b>28</b> | Providing and laying TAR paper below solid slab                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | <b>123.48</b> | <b>Sq.m.</b> | 55.55           | <b>6859.31</b>    |

| Item No. | Description of Item                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | Quantity | Unit  | Estimated Rates | Amount     |
|----------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|-------|-----------------|------------|
|          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |          |       | Rate In figures |            |
| 1        | 2                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | 3        | 4     | 5               | 6          |
| 29       | Providing and casting in -situ controlled cement concrete of M 40 grade for RCC crash Barrier with 20 mm down coarse aggregate of the required size including formwork, shuttering, placing in position, consolidation with mechanical vibrators curing finishing, deshuttering carefully, marking good the damages, fixing embedment, inserts, pockets, wherever necessary as directed and as per drawing with F3 type exposed concrete finish and formwork as directed by Engineer - in -charge, etc. complete as per specification.                                                                                                                                                                                                                                                                                                                                                                                                                    | 62.00    | Cu.m. | 5189.38         | 321741.56  |
| 30       | <p>Providing and placing the reinforcement in designed position, fixing, erecting or lowering in position TMT bars Fe-550D grade conforming to IS1786 for superstructure &amp; Crash Barrier all categories &amp; depth, at all levels. The rates includes for supply, loading, unloading, transporting to site, cutting, bending, hooking, placing, tying in position with contractor's own black annealed bindingwire, welding etc. Welding and supporting inposition to ensure line sand levels during concreting, maintaining proper cover / spacing, all leads &amp; lifts, etc. including contractor's own equipment, labour, supervisor, taxes, machineries, etc. complete as per drawings and specification.</p> <p>1) The waste cut pieces and laps shall not be included in the paying quantity.<br/> 2) Black annealed binding wire shall not be included in the paying quantity.<br/> 3) The work shall be done as per execution drawing.</p> | 59.12    | MT    | 72601.86        | 4292221.98 |

| Item No. | Description of Item                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | Quantity | Unit  | Estimated Rates | Amount    |
|----------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|-------|-----------------|-----------|
|          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |          |       | Rate In figures |           |
| 1        | 2                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | 3        | 4     | 5               | 6         |
| 31       | Providing and fixing metal expansion joints as per drawings. Details of expansion joint 50 x 50 x 6mm size two IS and 100 x 6mm MS plate with 6 x 20 x 25mm long hold fast @ 50 cm / cc on both sides of expansion joints.                                                                                                                                                                                                                                                                        | 67.20    | R.mt. | 2013.95         | 135337.45 |
| 32       | Providing and casting in-situ Reinforced controlled Cement Concrete M 30 grade with 20mm down coarse aggregate at any level including shuttering, mixing with batching plant, placing in position, consolidating with mechanical vibrators, curing, deshuttering carefully, making good the damages, fixing embedment, inserts, pockets, wherever necessary as directed for Approach Slab including all leads and lifts etc. complete as per specification and drawing.                           | 24.00    | Cu.m. | 5310.58         | 127453.92 |
| 33       | Providing and casting in-situ Reinforced controlled Cement Concrete M 40 grade for average 100 mm thick with 20mm down coarse aggregate at any level including shuttering, mixing with batching plant, placing in position, consolidating with mechanical vibrators, curing, deshuttering carefully, making good the damages, fixing embedment, inserts, pockets, wherever necessary as directed for wearing course including all leads and lifts etc. complete as per specification and drawing. | 71.00    | Cu.m. | 5611.56         | 398420.76 |

| Item No. | Description of Item                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | Quantity | Unit | Estimated Rates | Amount     |
|----------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|------|-----------------|------------|
|          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |          |      | Rate In figures |            |
| 1        | 2                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | 3        | 4    | 5               | 6          |
| 34       | <p>Providing and placing the reinforcement in designed position, fixing, erecting or lowering in position TMT bars Fe-550D for approach slab, wearing course &amp; kerb grade conforming to IS1786 for superstructure all categories &amp; depth, at all levels. The rates includes for supply, loading, unloading, transporting to site, cutting, bending, hooking, placing, tying in position with contractor's own black annealed bindingwire, welding etc. Welding and supporting inposition to ensure line sand levels during concreting, maintaining proper cover / spacing, all leads &amp; lifts, etc. including contractor's own equipment, labour, supervisor, taxes, machineries, etc. complete as per drawings and specification.</p> <p>1) The waste cut pieces and laps shall not be included in the paying quantity.<br/> 2) Black annealed binding wire shall not be included in the paying quantity.<br/> 3) The work shall be done as per execution drawing.</p> | 7.61     | MT   | 72601.86        | 552500.16  |
| 35       | Providing anti-corrosive treatment to HYSD reinforcement with Fusion Bonded Epoxy Coating (FBEC)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | 333.00   | MT   | 6206.45         | 2066747.85 |
| 36       | Providing, fabricating and fixing in position GI Drainage Spout arrangements having 100 mm dia. Pipe B class with necessary bend, fixing to GI chamber, GI grating, providing and applying one coat of primer & two coat of anticorrosive paint, etc. complete as per drawing and as per specifications.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | 42.00    | Each | 536.03          | 22513.14   |
| 37       | Providing and fixing marble slab including transporting ,engraving and painting all complete.<br>(ii) Size 60cm x 60cm x 4cm                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | 2.00     | Each | 824.01          | 1648.02    |

| Item No. | Description of Item                                                                                                                                                                                                                                                                     | Quantity | Unit  | Estimated Rates | Amount    |
|----------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|-------|-----------------|-----------|
|          |                                                                                                                                                                                                                                                                                         |          |       | Rate In figures |           |
| 1        | 2                                                                                                                                                                                                                                                                                       | 3        | 4     | 5               | 6         |
| 38       | Painting on Concrete/Steel Surfaces with Epoxy<br>Painting two coats including prime coat with epoxy paint of approved brand on concrete/steel surfaces after through cleaning of surface to give an even shade as per drawing and Technical Specification Clause 1701                  | 1971.50  | Sq.m. | 76.77           | 151352.25 |
| 39       | Providing and fixing in position Mild steel dowel bars in pier caps or abutment caps for anchorage in fixed end as per detailed drawings including cutting, bending and welding complete.                                                                                               | 105.60   | R.mt. | 339.88          | 35890.81  |
| 40       | Providing and fixing in position Mild steel dowel bars in pier caps or abutments caps for anchorage in free end as per detailed drawing including cutting, bending and welding complete.                                                                                                | 92.80    | R.mt. | 396.27          | 36774.18  |
| 41       | Providing and laying Extruded Biaxial Polypropylene Geogrid 30 KN and thickness of layer 0.75m up to 3 m height and height between 3 to 6m Extruded Biaxial Polypropylene Geogrid 30 KN and thickness of layer 0.6m as directed by Engineer In charge and as per detailed specification | 1548.80  | Sq.m. | 153.52          | 237771.78 |

| Item No. | Description of Item                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | Quantity | Unit  | Estimated Rates | Amount     |
|----------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|-------|-----------------|------------|
|          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |          |       | Rate In figures |            |
| 1        | 2                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | 3        | 4     | 5               | 6          |
| 42       | Providing and cast in situ controlled cement concrete of M-30 grade as per relevent code for reinforced cement concrete with 20mm down graded crushed stone aggregates of required size in foundation of Retaining Wall etc. & Sub-structure including form work shuttering and supporting arrangement (excluding cost of reinforcement ) and transporting concrete from batching plant by transit mixture, placing it in position, Compacting with needle Vibrator including Curing with all labour, material, machinery, all lead, lift etc complete as per drawing and Technical specification. | 721.00   | Cu.m. | 4772.25         | 3440792.25 |
| 43       | Providing Vertical joints between retaining walls, abutments, etc. & with necessary premoulded asphalt filler joint as per drawing & specification ( A) 12mm                                                                                                                                                                                                                                                                                                                                                                                                                                       | 150.40   | R.mt. | 702.12          | 105599.10  |
| 44       | Providing and laying in positions machine mixed Plain Ordinary Cement Concrete M10 grade for leveling course below foundation, approach slab, etc. at other places as directed by Engineer-in-charge with graded broken stone aggregate from 6mm to 20 mm including tamping, vibrating, leveling and curing complete with all formwork, dewatering wherever required including all materials, labours, plants, machineries & tools,all leads and lifts, etc.complete as per specification.                                                                                                         | 332.80   | Cu.m. | 3245.56         | 1080123.80 |
| 45       | Providing and casting in situ controlled cement concrete M-20 for R.C.C. return as per drawings including centering shuttering, scaffolding where necessary, laying vibrating, curing and finishing complete.(A) Height from 0.0 to 5.0 M.(3) RCC return (upto 10 ton)                                                                                                                                                                                                                                                                                                                             | 1487.90  | Cu.m. | 5078.31         | 7556017.90 |

| Item No. | Description of Item                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | Quantity | Unit | Estimated Rates | Amount     |
|----------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|------|-----------------|------------|
|          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |          |      | Rate In figures |            |
| 1        | 2                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | 3        | 4    | 5               | 6          |
| 46       | Earth work for embankment including breaking clods, dressing with all lead and lift including watering, rolling and consolidation of sub grade in layers at O.M.C to required dry density including filling the depression which occur during the process using vibratory roller 8 to 10 Tonne (c) From Borrow area with in 3.0 KM Lead                                                                                                                                                                   | 3375.00  | Cum  | 169.43          | 571826.25  |
| 47       | Construction of granular sub-base 150 thick by providing machine crushed B.T. material satisfying MORT&H specification (Fifth revision) of grading V including spreading in uniform layer with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC and compacting with vibratory roller to achieve the desired density etc. complete.                                                                                                                                   | 539.00   | Cum  | 712.05          | 383794.95  |
| 48       | Providing and filling in foundation with ordinary Cement concrete M-150 mix and providing necessary vertical pin headers including formwork, vibrating, ramming and curing complete.                                                                                                                                                                                                                                                                                                                      | 260.00   | Cum  | 3615.80         | 940108.00  |
| 49       | Construction of concrete road using tremix system with 20cm thick CC M 300 Concrete mixing conplast P-211 water reduction admixture @ 100 ml/bag of cement and harder 62.50ml/bag using fixing and removing 'C' Channels of required road depth leveling if placed concrete with surface vibrator, finishing the surface with power floter and towel tight brooming as directed with providing expansion joints 20 x 200mm and construction joint 20 x 20 mm using concrete cutter machine etc. complete. | 520.00   | Cum  | 6262.00         | 3256240.00 |
| 50       | Providing IS mark TMT Bar FE 500D reinforcement for R.C.C. work including bending, binding and placing in position complete upto floor two level                                                                                                                                                                                                                                                                                                                                                          | 19506.00 | Kg   | 76.21           | 1486552.26 |

| Item No. | Description of Item                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | Quantity | Unit | Estimated Rates | Amount    |
|----------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|------|-----------------|-----------|
|          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |          |      | Rate In figures |           |
| 1        | 2                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | 3        | 4    | 5               | 6         |
| 51       | Providing and laying 22.5 cms thick dry stone pitching including preparing the surface with 15 cms thick murrum bedding and including watering and providing 30 cms x 30cms pannel in cement concrete 1:3:6 at 3.0 meter center to center vertically & Horizontally and filling the voids of rubble with quarry spalls and murrum including ramming and watering with flush pointing on dry stone pitching and uncoursed stone masonry with C.M. 1:3 (1 Cement:3 Sand) etc. complete.(Including Supplying and Spreading Murram)                                                                                                                                                                                                                                                                                                                                                           | 604.00   | Sqmt | 816.48          | 493153.92 |
| 52       | Road marking with hot applied thermoplastic paints with reflectorising glass beads on bitumin surface. Providing and laying a hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads@ 250gms per sqm area, thickness of 2.5mm is excluding of surface applied, glass beads as per IRC:35-2015. The finished surface to be level, uniform and free from streaks and holes. zebra patta /bump patta lane/center line/ edge line/cut patta.The white color marking should provide luminance coefficient on cement road shall be min 130 mcd/m2/lux and Asphalt road shall be min 100 mcd/m2/lux during the service life during the day time.The marking should meet the performance criteria for night time reflectivity, wet reflectivity and skid resistance as mentioned In the section-15 of IRC 35-2015 Warranty for reflectivity shall be for two years. | 255.00   | Sqm  | 367.72          | 93768.60  |

| Item No. | Description of Item                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | Quantity | Unit | Estimated Rates | Amount   |
|----------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|------|-----------------|----------|
|          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |          |      | Rate In figures |          |
| 1        | 2                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | 3        | 4    | 5               | 6        |
| 53       | Cat Eye/ Road Stud/ RPM:- Supplying Raised Pavement Markers made of polycarbonate and ABS moulded body and reflective panels with Micro compressed molding with micro prismatic lens (No Glass bead lens) capable of providing total internal reflection of the light entering the lens face and shall support a load of 13635 kgs.tested in accordance to ASTM D,4280 Type H and complying to Specifications of Category A of MORTH Circular No RW/NH/33023/10-97 - DO III Dt 11.06. 1997. The height,width and length shall not exceed 20 mm, 130 mm and 130 mm and with minimum reflective area of 13 Sqcm on each side and the slope to the base shall be 35 +/- 5 degree.The body of the marker should having finger grip for easy and accurate placement and application with epoxy / bituminous Adhesive as recommended by the manufacturer of the marker. The color of the marker should be as per the IRC 35-2015 and as directed by Engineer-In-charge. | 63.00    | Nos. | 217.40          | 13696.20 |

| Item No. | Description of Item                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | Quantity | Unit | Estimated Rates | Amount   |
|----------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|------|-----------------|----------|
|          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |          |      | Rate In figures |          |
| 1        | 2                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            | 3        | 4    | 5               | 6        |
| 54       | Direction (Junction) Sign :-Providing and fixing sign boards made out of 2mm aluminum sheet / 4mm ACP (Aluminum composite Panel); size 244x122 cms. rectangular as per design of IRC-67-2012. Pre treated with phospheting process & acid etching; coated with one coat of epoxy primer and two coats of best quality epoxy paint ; reflectorised with High Intensity Prismatic Grade retro reflective sheeting of Type-4 as per ASTM D-4956 and latest M.O.S.T. Specifications; 4.0mtr (2 Nos.) long stand post of Iron Angle 75 x 75 x 6mm / 65NB Circular MS Pipe as required and frame fabricated from suitable size iron angle of 50x50x5mm; painted with best quality epoxy coatings in black and white bends. The details of symbol for each board shall be as per the instruction of engineer in charge. The fixing at site shall be in 1:2:4 CC block of size 45 x 45 x 60 Cms. for each leg including excavation, curing etc. complete under the supervision of engineer in charge. A warranty for 7 years for the Retro reflective sheeting from original manufacturer & a certified copy of 3 year outdoor exposure test report from third party test lab for the product offered shall be submitted by contractor. (B) Class-B Type-4 Retro Reflective sheeting | 2.00     | Nos. | 21287.50        | 42575.00 |

| Item No. | Description of Item                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | Quantity | Unit | Estimated Rates | Amount   |
|----------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|------|-----------------|----------|
|          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |          |      | Rate In figures |          |
| 1        | 2                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | 3        | 4    | 5               | 6        |
| 55       | Cautionary Warning Sign :-Providing and fixing sign boards made out of 2mm aluminium sheet / 4mm ACP (Aluminum composite Panel); size 90 x 90 x 90 cms. equilateral triangle as per design of IRC-67-2012. Pre treated with phospheting process & acid etching; coated with one coat of epoxy primer and two coats of best quality epoxy paint ; reflectorised with High Intensity Prismatic Grade retro reflective sheeting of Type-4 as per ASTM D- 4956 and latest M.O.S.T. Specifications; 3.6mtr long stand post of Iron Angle 75 x 75 x 6mm / 65NB Circular MS Pipe as required and frame fabricated from suitable size iron angle of 35 x 35 x 3mm; painted with best quality epoxy coatings in black and white bends. The details of symbol for each board shall be as per the instruction of engineer in charge. The fixing at site shall be in 1:2:4 CC block of size 45 x 45 x 60 Cms. for each leg including excavation, curing etc. complete under the supervision of engineer in charge. A warranty for 7 years for the Retro reflective sheeting from original manufacturer & a certified copy of 3 year outdoor exposure test report from third party test lab for the product offered shall be submitted by contractor. (B) Class-B Type-4 Retro Reflective sheeting | 4.00     | Nos. | 3906.18         | 15624.72 |

| Item No. | Description of Item                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | Quantity | Unit | Estimated Rates | Amount  |
|----------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|------|-----------------|---------|
|          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |          |      | Rate In figures |         |
| 1        | 2                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | 3        | 4    | 5               | 6       |
| 56       | Hazard Marker Sign :-Providing and fixing sign boards made out of 2mm aluminium sheet / 4mm ACP (Aluminum composite Panel); size 90x30 cms. rectangular as per design of IRC-67-2012. Pre treated with phospheting process & acid etching; coated with one coat of epoxy primer and two coats of best quality epoxy paint ; reflectorised with High Intensity Prismatic Grade retro reflectivesheeting of Type-4 as per ASTM D-4956 and latest M.O.S.T.Specifications; 1.8mtr long stand post of Iron Angle 75 x 75 x 6mm / 65NB Circular MS Pipe as required and frame fabricated from suitable size iron angle of 35 x 35 x 3mm; painted with bestquality epoxy coatings in black and white bends. The details of symbol for each board shall be as per the instruction of engineer in charge. The fixing at site shall be in 1:2:4 CC blockof size 45 x 45 x 60 Cms. for each leg including excavation, curing etc.complete under the supervision of engineer in charge. A warranty for 7 years for the Retro reflective sheeting from original manufacturer & a certified copy of 3 year outdoor exposure test report from third party test lab for the product offered shall be submitted by contractor. (B) Class-B Type-4 Retro Reflective sheeting | 2.00     | Nos. | 3518.68         | 7037.36 |

| Item No. | Description of Item                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | Quantity | Unit | Estimated Rates | Amount   |
|----------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|------|-----------------|----------|
|          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |          |      | Rate In figures |          |
| 1        | 2                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | 3        | 4    | 5               | 6        |
| 57       | Village name Sign :-Providing and fixing sign boards made out of 2mm aluminium sheet / 4mm ACP (Aluminum composite Panel); size 90x60 cms. rectangular as per design of IRC-67-2012. Pre treated with phospheting process & acid etching; coated with one coat of epoxy primer and two coats of best quality epoxy paint ; reflectorised with High Intensity Prismatic Grade retro reflectivesheeting of Type-4 as per ASTM D-4956 and latest M.O.S.T.Specifications; 3.3mtr long stand post of Iron Angle 75 x 75 x 6mm / 65NB Circular MS Pipe as required and frame fabricated from suitable size iron angle of 35 x 35 x 3mm; painted with bestquality epoxy coatings in black and white bends. the details of symbol or inscription / numerals for each board shall be as per the instruction of engineer in charge. The fixing at site shall be in 1:2:4 CC blockof size 45 x 45 x 60 Cms. for each leg including excavation, curing etc.complete under the supervision of engineer in charge. A warranty for 7 years for the Retro reflective sheeting from original manufacturer & a certified copy of 3 year outdoor exposure test report from third party test lab for the product offered shall be submitted by contractor. (B) Class-B Type-4 Retro Reflective sheeting | 2.00     | Nos. | 6397.43         | 12794.86 |

| Item No. | Description of Item                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | Quantity | Unit | Estimated Rates | Amount  |
|----------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|------|-----------------|---------|
|          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |          |      | Rate In figures |         |
| 1        | 2                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | 3        | 4    | 5               | 6       |
| 58       | <p>Facility Informatory Sign :-Providing and fixing sign boards made out of 2mm aluminum sheet / 4mm ACP (Aluminum composite Panel); size 80 x 60 cms. rectangular as per design of IRC-67-2012. Pre treated with phospheting process &amp; acid etching; coated with one coat of epoxy primer and two coats of best quality epoxy paint ; reflectorised with High Intensity Prismatic Grade retro reflective sheeting of Type-4 as per ASTM D-4956 and latest M.O.S.T. Specifications; 3.6mtr long stand post of Iron Angle 75 x 75 x 6mm / 65NB Circular MS Pipe as required and frame fabricated from suitable size iron angle of 35 x 35 x 3mm; painted with best quality epoxy coatings in black and white bends. The details of symbol for each board shall be as per the instruction of engineer in charge. The fixing at site shall be in 1:2:4 CC block of size 45 x 45 x 60 Cms. for each leg including excavation, curing etc. complete under the supervision of engineer in charge. A warranty for 7 years for the Retro reflective sheeting from original manufacturer &amp; a certified copy of 3 year outdoor exposure test report from third party test lab for the product offered shall be submitted by contractor. (B) Class-B Type-4 Retro Reflective sheeting.</p> | 2.00     | No.  | 3990.64         | 7981.28 |

| Item No. | Description of Item                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | Quantity | Unit | Estimated Rates | Amount   |
|----------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|------|-----------------|----------|
|          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |          |      | Rate In figures |          |
| 1        | 2                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | 3        | 4    | 5               | 6        |
| 59       | <p>Chevron Sign :-Providing and fixing sign boards made out of 2mm aluminium sheet / 4mm ACP (Aluminum composite Panel); size 60 x 50 cms.rectangular as per design of IRC-67-2012. Pre treated with phospheting process &amp; acid etching; coated with one coat of epoxy primer and two coats of best quality epoxy paint ; reflectorised with high intensity Prismatic Grade retro reflective sheeting of Type-4 as per ASTM D-4956 and latest M.O.S.T. Specifications; 3.3mtr long stand post of Iron Angle 75 x 75 x 6mm / 65NB Circular MS Pipe as required and frame fabricated from suitable size iron angle of 35 x 35 x 3mm; painted with best quality epoxy coatings in black and white bends. The details of symbol or inscription/ numerals for each board shall be as per the instruction of engineer in charge. The fixing at site shall be in 1:2:4 CC block of size 45 x 45 x 60 cms for each leg, including excavation curing etc. complete under the supervision of Engineer-In-Charge. A warranty for 7 years for the Retro reflective sheeting from original manufacturer &amp; a certified copy of 3 year outdoor exposure test report from third party test lab for the product offered shall be submitted by contractor. (B) Class-B Type-4 Retro Reflective sheeting.</p> | 10.00    | No.  | 3711.75         | 37117.50 |

| Item No. | Description of Item                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | Quantity | Unit | Estimated Rates | Amount   |
|----------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|------|-----------------|----------|
|          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |          |      | Rate In figures |          |
| 1        | 2                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | 3        | 4    | 5               | 6        |
| 60       | Regulatory / Mandatory Sign :-Providing and fixing sign boards made out of 2mm aluminum sheet / 4mm ACP (Aluminum composite Panel); size 60 cms. Dia Circle as per design of IRC-67-2012. Pre treated with phospheting process & acid etching; coated with one coat of epoxy primer and two coats of best quality epoxy paint ; reflectorised with High Intensity Prismatic Grade retro reflective sheeting of Type-4 as per ASTM D-4956 and latest M.O.S.T. Specifications; 3.6mtr long stand post of Iron Angle 75 x 75 x 6mm / 65NB Circular MS Pipe as required and frame fabricated from suitable size iron angle of 35 x 35 x 3mm; painted with best quality epoxy coatings in black and white bends. The details of symbol for each board shall be as per the instruction of engineer in charge. The fixing at site shall be in 1:2:4 CC block of size 45 x 45 x 60 Cms. for each leg including excavation, curing etc. complete under the supervision of engineer in charge. A warranty for 7 years for the Retro reflective sheeting from original manufacturer & a certified copy of 3 year outdoor exposure test report from third party test lab for the product offered shall be submitted by contractor. (B) Class-B Type-4 Retro Reflective sheeting. | 4.00     | No.  | 3540.12         | 14160.48 |

| Item No.  | Description of Item                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | Quantity       | Unit        | Estimated Rates | Amount           |
|-----------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------|-------------|-----------------|------------------|
|           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |                |             | Rate In figures |                  |
| 1         | 2                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | 3              | 4           | 5               | 6                |
| <b>61</b> | Type=B THRIE : Metal Beam Crash Barrier<br>Providing and directing a "Thrie" beam metal crash barrier comprising of 3 mm thick corrugated sheet metal beam rail, 85 cm above road/ground level, fixed on ISMC series channel vertical post, 150x75x5mm spaced 2 m centre to centre, 2 m high with 1.15 m below ground level. The vertical post fixing at site shall be in M25 grade cement concrete of size 35x35x120 cms. for each post including excavation curing etc. completed. All steel parts and fittings to be galvanised by hot dip process all fittings to conform to IS 1367 and IS 1364 metal beam rail to be fixed on the vertical post with a spacer of channel section 150x75x5 mm, 550 mm long completed as per MORTH specification clause 810 including butt welding to all nuts & bolts & including 3 mm ACM type reflector 100 mm wide & 4.5 m long, type 4 class B high intensity Grad sheeting as per IRC 67:2012 etc. completed as per instruction of Engineer in charge. Also red/yellow color strip of size 100x300 mm shall be fixed on vertical front side of post for better night visibility. The spacer post, thrie beam rail shall be cold roll formed & galvanized with 550 gm/sq.mtr. | <b>165.60</b>  | <b>Rmt</b>  | 4632.22         | <b>767096.07</b> |
| <b>62</b> | Providing and fixing ordinary kilometer stone of precast C.C. 1:2:4 including necessary reinforcement as per I.R.C. type design in C.C. 1:4:8 including painting and lettering etc. complete. For O.D.R./ V.R.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | <b>1.00</b>    | <b>Nos.</b> | 1290.56         | <b>1290.56</b>   |
| <b>63</b> | Providing and fixing guard stone as per I.R.C. type design including white washing etc. complete. (ii) Fixing in C.C. 1:5:10                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | <b>386.00</b>  | <b>Nos.</b> | 327.69          | <b>126488.34</b> |
| <b>64</b> | Box cutting the road surface to proper slope and camber for making a base for road work including removing the excavated stuff and depositing on the road side slope as directed upto 50Mt.lead.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | <b>1202.00</b> | <b>Cum</b>  | 104.20          | <b>125248.40</b> |

| Item No. | Description of Item                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | Quantity | Unit | Estimated Rates | Amount    |
|----------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|------|-----------------|-----------|
|          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |          |      | Rate In figures |           |
| 1        | 2                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | 3        | 4    | 5               | 6         |
| 65       | Water Bound Macadam Grading-I (By Manual Means) Providing, laying, spreading and compacting stone aggregates of 90 to 45.00mm sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill up the interstices of coarse aggregate, watering and compacting to the required density. (As per Technical Specification Clause 404-4.9A(i)) | 678.00   | Cum  | 1336.49         | 906138.28 |
| 66       | Water Bound Macadam Grading-II (By Manual Means) Providing, laying, spreading and compacting stone aggregates of 63 to 45mm sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill up the interstices of coarse aggregate, watering and compacting to the required density.                                                       | 40.30    | Cum  | 1078.17         | 43450.25  |
| 67       | Providing and applying priming coat with emulsion SS1 grade at the rate of 7.50 kg/ 10 Sq.mt. including cost of asphalt and preparing the surface heating, and applying etc. complete.                                                                                                                                                                                                                                                                                                                                          | 935.00   | Sqm  | 62.50           | 58437.50  |

| Item No. | Description of Item                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | Quantity | Unit | Estimated Rates | Amount    |
|----------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|------|-----------------|-----------|
|          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |          |      | Rate In figures |           |
| 1        | 2                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | 3        | 4    | 5               | 6         |
| 68       | Providing & Laying 20mm thick mix seal surfacing using stone chipping and aggregate as per MORT&H specification and asphalt grade VG-30 for mixing at the rate of 4.5% of total mix including heating the aggregate and asphalt by drum mixing plant and including using asphalt grade VG-30 for tack coat at the rate of 2.5kg/10sq.mt. spreading with vibratory roller including providing all materials equipments tools and plants oil, kerosene, firewood , labour charges etc. complete                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | 43.00    | MT   | 2642.16         | 113612.88 |
| 69       | Men at work (Heavy) Sign : Providing and fixing sign boards made out of 2mm aluminium sheet / 4mm ACP (Aluminium Composite panel) size 120cm. x 90cm. as per design of IRC 67-2012. Pretreated with phosphating process & acid etching; coated with one coat of epoxy primer and two coats of best quality epoxy paint; reflectorised with Micro Prismatic Grade Retro Reflective sheeting of Type-11 as per ASTM D-4956 and latest MOST specification; 3.6mtr. long stand post (2-Nos.) of Iron Angle 75 x 75 x 6mm / 65NB Circular MS Pipe as required and frame fabricated from suitable size iron angle of 50 x 50 x 5mm; painted with best quality epoxy coatings in black and white bands, the details of symbol or inscription / numerals for each board shall be as per the instruction of engineer-in-charge. The fixing at site shall be in 1:2:4 CC block of size 45 x 45 x 60cms. for each leg including excavation, curing etc. complete under the supervision of engineer in charge. A Warranty for 7 years for the Retro reflective sheeting from original manufacturer & a certified copy of 3-years outdoor exposure test report from third party test lab for the product offered shall be submitted by | 2.00     | No   | 12211.91        | 24423.82  |

| Item No. | Description of Item                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | Quantity | Unit | Estimated Rates | Amount   |
|----------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|------|-----------------|----------|
|          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |          |      | Rate In figures |          |
| 1        | 2                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | 3        | 4    | 5               | 6        |
| 70       | <p>Diversion Ahead Sign :- Providing and fixing sing boards made out of 2mm aluminium sheet / 4mm ACP (Alluminium Composite Panel) ; size 180 x 60cms. rectangle as as per the design of IRC-67-2012 pre treated with phospheting process &amp; acid etching; coated with one coat of epoxy primer and two coats of best quality epoxy paint; reflectorised with Micro Grade retro reflective sheeting of type-11 as per ASTM D-4956 and latest MOST specification; 3.1mtr. long stand post (2-Nos.) of Iron Angle 50 x 50 x 5mm / 50 NB circular MS pipe as required and frame fabricated from suitable size iron angle of 35 x 35 x 5mm; painted with best quality epoxy coatings in black and white bends. The details of symbol for each board shall be as per the instruction of engineer in charge. The fixing at site shall be in 1:2:4 CC block of size 45 x 45 x 60cms. for each leg including excavation, curing etc. complete under the supervision of engineer in charge. A warranty for 10 years for the Retro reflective sheeting from original manufactuerer &amp; a certified copy of 3 years outdoor exposure test report from third party test lab for the product offered shall be submitted by contractor (A) Class-C Type-11 Retro Reflective Sheeting.</p> | 2.00     | No   | 10671.66        | 21343.32 |

| Item No. | Description of Item                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | Quantity | Unit | Estimated Rates | Amount     |
|----------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|------|-----------------|------------|
|          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |          |      | Rate In figures |            |
| 1        | 2                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | 3        | 4    | 5               | 6          |
| 71       | Supplying and fixing reinforced concrete heavy duty non-pressure pipes with collars for culverts including setting and joining the pipes in C.M. 1:2 watering and laying (To level of slops of I.S. 458 / 1971 Class NP3 casted by vertically vibrated technology of following internal diameter. (v) 900 mm dia.                                                                                                                                                                                                          | 95.00    | Rmt  | 3246.19         | 308388.05  |
| 72       | Earthwork in cutting in all sorts of soil and soft murrum including conveying and spreading the stuff, embankment as and where directed within 200meters from the end of the cutting with all required lead and lift                                                                                                                                                                                                                                                                                                       | 240.00   | Cum  | 127.74          | 30657.60   |
| 73       | Construction of concrete road using tremix system with 15cm thick controlled C.C. M-250 concrete mixing conplast P-211 water reduction admixture @ 100 ml/bag of cement and hardner 62.50 ml/bag using fixing and removing 'C' channels of required road depth levelling if placed concrete with surface vibrator, finishing the surface with power floter and towel tight brooming as directed with providing expansion joints 20 x 200 mm and construction joints 20 x 20 mm using cocnrete cutter machine etc. complete | 461.30   | Cum  | 6099.64         | 2813763.93 |
| 74       | Providing and fixing in position FE 500D TMT bar reinforcement including cutting, bending and tying complete as per detailed drawings. (A) R.C.C. Kerb. (B) R.C.C. Footpath. (C) R.C.C. Approch slab. (D) Wearing Coat.                                                                                                                                                                                                                                                                                                    | 6.86     | MT   | 72601.86        | 498048.76  |
| 75       | Providing and laying in position FE 500D TMT bar reinforcement including cutting, bending, hooking and tying complete as per detailed drawings for the following. (A) Piers (B) Abutments (C) R.C.C. Returns                                                                                                                                                                                                                                                                                                               | 0.84     | MT   | 73217.52        | 61502.72   |

| Item No. | Description of Item                                                                                                                                                                                                                       | Quantity | Unit | Estimated Rates | Amount    |
|----------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|------|-----------------|-----------|
|          |                                                                                                                                                                                                                                           |          |      | Rate In figures |           |
| 1        | 2                                                                                                                                                                                                                                         | 3        | 4    | 5               | 6         |
| 76       | Dismantling C.I. pipes G.S.W. pipes and A.C. rain water pipes with fittings and clamps including stacking the materials with all lead and lift. (for any dia, of pipe)                                                                    | 25.00    | Rmt  | 73.02           | 1825.50   |
| 77       | Excavation for foundation upto 1.5 m depth including sorting out and stacking of useful materials and disposing of the excavated stuff upto 50 Meter lead. (B) Dense or Hard soil.                                                        | 70.80    | Cum  | 241.79          | 17118.73  |
| 78       | Excavation for foundation upto 1.5 m depth including sorting out and stacking of useful materials and disposing off the excavated stuff upto 50 Meter lead. (C) Hard Murrum                                                               | 60.70    | Cum  | 412.00          | 25008.40  |
| 79       | Providing & casting in situ ordinary cement concrete M-150 mix and providing necessary pin headers including shuttering, scaffolding, laying, vibrating, curing and finishing complete without V-Groves. (A) Height from 0.0 M. to 5.0 M. | 107.20   | Cum  | 3818.54         | 409347.49 |
| 80       | Filling available excavated earth (excluding rock) in trenches. plinth, sides of foundations etc. in layers not exceeding 20 cm. in depth consolidating each disposed layer by ramming and watering.                                      | 111.00   | Cum  | 130.39          | 14473.29  |
| 81       | Rolling of earthwork in layers with power roller including filling in depressions which occur during the process and Watering of earth work as directed.                                                                                  | 106.40   | Cum  | 22.48           | 2391.87   |
| 82       | Providing and casting in situ controlled cementconcrete M- 200 for average 75/150 mm thick wearing coat laid as directed dincluding tamping, vibrating, finishing, curing and filling in joints with bitumen complete.                    | 40.30    | Cum  | 5187.83         | 209069.55 |

| Item No. | Description of Item                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | Quantity | Unit | Estimated Rates | Amount   |
|----------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|------|-----------------|----------|
|          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |          |      | Rate In figures |          |
| 1        | 2                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | 3        | 4    | 5               | 6        |
| 83       | Providing and fixing Flood Gauge Flood Gauge Post mark of C angle size 100mm x 50mm x 6mm thick of length 2.00mt. height fixed in head wall 0.50mt. and 1.50mt. outside with painting and lettering with radium color as direct.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | 6.00     | No   | 1134.23         | 6805.38  |
| 84       | Cautionary Warning Sign :-Providing and fixing sing boards made out of 2mm aluminium sheet; size 90 x 90 x 90 cms. equilateral triangle as per design of IRC67-1977. Pre treated with phospheting process & acid etching; coated with one coat of epoxy primer and two coats of best quality epoxy paint; reflectorised with retro reflective sheeting as per latest M.O.S.T. Specifications; 3.1m long stand postand frame fabricated from suitable sizeiron angle of 35 x 35 x 3mm, 75 x 75 x 6mm as required; painted with bestquality epoxy coatings in black andwhite bends. The details of symbol foreach board shall be as per theinstruction of engineer in charge. The fixing at site shall be in 1:2:4 CC block of size 45 x 45 x 60 Cms. for each leg including excavation, curing etc. complete under the supervision of engineer in charge. (A) Engineer Grade (VR) | 6.00     | No   | 3808.65         | 22851.90 |
| 85       | Dismantaling the existing structure including removing and stacking the dismantelled materials as and where directed.<br>(B) Rubble Masonry.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | 19.00    | Cum  | 389.73          | 7404.87  |
| 86       | Supplying and fixing reinforced concrete heavy duty non- pressure pipes with collars for culverts carrying heavy traffic as per IS 458-1991 specifications including setting the pipes in C.M. 1:2 watering and laying (to level or slopes) of class NP3 of following internal daimeters. (v) 600mm dia.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | 30.00    | Rmt  | 1951.69         | 58550.70 |

| Item No. | Description of Item                                                                                                                                                                                          | Quantity | Unit | Estimated Rates | Amount  |
|----------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|------|-----------------|---------|
|          |                                                                                                                                                                                                              |          |      | Rate In figures |         |
| 1        | 2                                                                                                                                                                                                            | 3        | 4    | 5               | 6       |
| 87       | Providing and fixing ordinary Kilometer stone of precast C.C. 1:2:4 including necessary reinforcement as per I.R.C. type design in C.C. 1:4:8 including painting,lettering etc. complete (For VR Road)       | 1.00     | No   | 704.33          | 704.33  |
| 88       | Providing and fixing Hectometer as per I.R.C. type design including painting, lettering etc. complete.(ii) Fixing in C.C. 1:5:10                                                                             | 1.00     | No   | 356.49          | 356.49  |
| 89       | Providing and fixing Junction board of M.S. plates and angles as per standard I.R.C. design including fixing in C.C. 1:4:8 with necessary excavation painting figuring and lettering on board etc. complete. | 1.00     | No   | 5236.69         | 5236.69 |
| 90       | Providing and fixing village name boards as per standard I.R.C. type design of steel plate including painting lettering etc. complete with fixing in C.C. 1:4:8 block with necessary excavation.             | 1.00     | No   | 3437.59         | 3437.59 |

| Item No.  | Description of Item                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | Quantity     | Unit        | Estimated Rates | Amount          |
|-----------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------|-------------|-----------------|-----------------|
|           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |              |             | Rate In figures |                 |
| 1         | 2                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | 3            | 4           | 5               | 6               |
| <b>91</b> | Citizen's Information Board- Providing and fixing of typical MMGSY information board as per instruction. Two M.S. sheets of 3 mm thick of 900mm x 750mm size fixed at top & bottom duly rivetted with MSangles of 25x25x5mm thick M.S. angle shall be welded by two vertical M.S. angle of 5mm thick to 75mm x 75mm of 12 SWG square tubes posts duly embedded in cement concrete M-15 grade blocks of 600mmx 600mm x 750mm below ground level. The letters & figure of anyshade reflectorised with high intensity prismatic grade retro reflectivesheeting of Type-4 as per ASTM D-4956 and latest MORD specifications; All sections of framed posts and steel tube will be painted with primer and two coats of epoxy paints as per drawing Clause 1701 and Annexure 1700.1 (10.16). (A) Class-B high intensity grade retro reflective sheeting. | <b>1.00</b>  | <b>No</b>   | 7759.83         | <b>7759.83</b>  |
| <b>92</b> | Providing and fixing indicator stone of approved stone as per I.R.C. type design in C.C. 1:4:8 including white washing etc. complete. (i) Fixing in Earth                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | <b>17.00</b> | <b>Each</b> | 102.84          | <b>1748.28</b>  |
| <b>93</b> | Supplying and fixing road sign board of M.S. plates and angle iron including painting, lettering etc. complete including fixing in C.C. 1:4:8 with necessary excavation etc. complete as per I.R.C. type design. (ii) Reflective type                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | <b>6.00</b>  | <b>Each</b> | 3072.98         | <b>18437.88</b> |

| Item No. | Description of Item                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | Quantity | Unit | Estimated Rates | Amount   |
|----------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|------|-----------------|----------|
|          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |          |      | Rate In figures |          |
| 1        | 2                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | 3        | 4    | 5               | 6        |
| 94       | Village Name / Bump Ahead Sign:- Providing and fixing sing boards made out of 2mm aluminium sheet; size 90 x 60cms. rectangle as as per the design of IRC-67-1977 pre treated with phospheting process & acid etching; coated with one coat of epoxy primer and two coats of best quality epoxy paint; reflectorised with retro reflective sheeting as per latest M.O.S.T. Specifications; Letters and numerals should be as per IRC-30-1968, 3.1m long (2 nos) stand post and frame fabricated from suitable size iron angle of 50 x 50 x 5mm painted with best quality epoxy coatings in black and white bends. the details of symbol or inscription / numerals for each board shall be as per the instruction of engineer in charge. The fixing at site shall be in 1:2:4 CC block of size 45 x 45 x 60cms. for each leg. including excavation curing etc. complete under the supervision of engineer in charge. (A) Engineer Grade (VR) | 4.00     | No   | 5045.36         | 20181.44 |

| Item No. | Description of Item                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | Quantity | Unit | Estimated Rates | Amount      |
|----------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|------|-----------------|-------------|
|          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |          |      | Rate In figures |             |
| 1        | 2                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | 3        | 4    | 5               | 6           |
| 95       | Cat Eye / Road Stud / RPM: Supplying of Molded Twin Shanks Raised Pavement Markers made of polycarbonate and ABS moulded body and reflective panels with micro prismatic lens capable of providing total internal reflection of the light entering the lens face and shall support a load of 13635 kgs. tested in accordance to ASTM D 4280 Type H and complying to Specifications of Category A of MORTH Circular No RW/NH/33023/10-97 DO III Dt 11.06. 1997. the height, width and length shall not exceed 20 mm, 130 mm and 130 mm and with minimum reflective area of 13 Sqcm on each side and the slope to the base shall be 35 +/- 5 degree. The strength of detachment of the integrated cylindrical shanks, (of diameter not less than 19 +/- 2 mm and height not less than 30+/- 2 mm) from the body is to be a minimum value of 500 Kgf. Fixing will be by drilling holes on the road for the shanks to go inside, without nails and using epoxy resin based adhesive as per manufacturers recommendation and The color of the marker should be as per the IRC 35-2015 and as directed by Engineer- in-charge. | 116.00   | No   | 326.23          | 37842.68    |
|          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |          |      |                 | 97007994.86 |

**Deputy Executive Engineer**  
**Panchayat ( R&B ) Sub Division**  
**Vallabhipur**

**Executive Engineer**  
**Panchayat (R&B) Division**  
**Bhavnagar**

I/We am/are willing to carry out the work at .....% above/below (percent should be written in figures and words) of the estimated rates mentioned above. Amount of my/our tender works out as under.

| Item No. | Description of Item | Quantity | Unit | Estimated Rates | Amount |
|----------|---------------------|----------|------|-----------------|--------|
|          |                     |          |      | Rate In figures |        |
| 1        | 2                   | 3        | 4    | 5               | 6      |

**\*Estimated amount**

**Put to tender**                      **Rs.97007994.86**  
**Deduct .....** % below **Rs.....**  
**Net**                                      **Rs. ....**  
**In words .....**

**\*( please strike out whichever is not applicable)**

**Notes : -**

- 1 The Contractor shall exhibition board with detailed specification and details of work as directed by the Engineer – In – Charge for which no extra payment shall bemade.
- 2 The labourcess will be deducted as per prevailing rules i.e. 1% of the work done
- 3 GST and Income tax TDS will be deducted at a source while making payments of bills.

- 4 In all R.C.C. Items in Rate Analysis Standard Cement Consumption has been taken as per Govt G.R.: PRC-10/2017 Cement Consumption/16/C Date: 11/05/2017 as stated in S.O.R. therefore in R.C.C. items where the reisa change as per actual mix design the cost of difference of cement consumption have been deducted from the rate of original item at the rate of input rate mentioned in all the tender.

- 5 All Credit amount of 930512.31/- (Rupees ) shall be recovered from the running bill in which dismantle item recorde for payment.

**Signature of Bidder**