

Current Tender Details

Tender ID: 282008	Notice No.: 32/2025-26 of Bhavnagar Sr. No.1	Last Date For Bid Submission:: 16-03-2026 18:00:00
ECV: 9989232.70	Name of Work: Construction of New Structure of Bhavnagar District Package No.RPC-2/BVN/MMGSY/Normal/2025-26/P.02 Ta.Shihor , Dist.; Bhavnagar	Location: Bhavnagar
Open/WORKS	Client Name : Roads and Buildings	Sub Department : Bhavnagar Panchayat Division

Name of work :- Construction of New Structure of Bhavnagar District Package No.RPC-2/BVN/MMGSY/Normal/2025-26/P.02 Ta.Shihor , Dist.; Bhavnagar

BILL OF QUANTITIES

Item No.	Description of Item (With brief specification and reference to book of Specification)	Quantity	Unit	Rate	Amount
1	Excavation for foundation upto 1.5m depth including sorting out and stacking of useful materials and disposing of the excavated stuff upto all lead. Dense or hard soil.	497.00	One Cum	259.93	129185.21
2	Excavation for foundation upto 1.5m depth including sorting out and stacking of useful materials and disposing of the excavated stuff upto all lead. Hard Murrum	375.00	One Cum	442.90	166087.50
3	Providing and casting in situ ordinary cement concrete M-150 mix and providing necessary pin headers including shuttering, scaffolding, laying vibrating, curing and finishing complete Without V-Grooves For all Hieght.	1058.70	One Cum	3938.30	4169478.21
4	Providing and filling in foundation with ordinary cement concrete M-100 mix and providing necessary vertical pin headers incl. Formwork, vibrating, ramming and curing complete.	345.00	One Cum	3362.24	1159972.80
5	Construction of concrete road using tremix system with 20cm thick controlled M-200 concrete mixing conplast P-211 water reduction admixture @ 100ml/bag of cement and hardner 62.50ml. /bag using fixing and removing "C" channels of required road depth levelling if placed concrte with surface vibrator, finishing the surface with power floater and towel tight brooming as directed with providing expantion joints 20x200mm and contraction joints 20x20mm using concrete cutter machine etc. complete.	172.50	One Cum	6109.60	1053906.00
6	Providing and casting in situ Contolled cement concrete- M-200 for average 75/150mm thick wearing coat laid as directed incuding. tamping, vibrating, finishing, curring and filling in joints with bitumen complete.	202.70	One Cum	5320.24	1078412.65

Item No.	Description of Item (With brief specification and reference to book of Specification)	Quantity	Unit	Rate	Amount
7	Providing and laying weep hole in Abutment and returns by using A.C pipe of 100mm. Incl. fixing in proper grade and jointing the complete as per detailed specification.	167.00	One No	62.93	10509.31
8	Providing and laying in Position FE - 500/500D TMT bar reinforcement including cutting, bending, hooking and tying complete as per detailed drawings for the following (A) Piers (B) Abutments (C) Returns (D) Walls etc.	7.130	One MT	73858.69	526612.46
9	Providing and Fixing in position FE-500/500D TMT bar reinforcement including cutting, bending, hooking, and tying complete as per detailed drawaing (A)RCC kerb (B) RCC Footpath (B) RCC Solid Slab/ App. Slab / Wearing coat.	5.140	One MT	73243.01	376469.07
10	Filling available excavated earth (excluding rock) in trenches plinth sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering.	857.00	One Cum	137.47	117811.79
11	Supplying and fixing reinforced concrete heavy duty non presure pipes with collars for culverts carrying heavy traffic as per IS 458-1991 specification including setting and joinng the pipes in C.M. 1:2 watering and laying (to level or slope) of I.S. Class NP-3 of following internal diameter with all lead and lift. (i) 900mm Dia.	50.00	One Rmt.	3469.25	173462.50
12	Supplying and fixing reinforced concrete heavy duty non presure pipes with collars for culverts carrying heavy traffic as per IS 458-1991 specification including setting and joinng the pipes in C.M. 1:2 watering and laying (to level or slope) of I.S. Class NP-3 of following internal diameter with all lead and lift. (i) 1200mm Dia.	40.00	One Rmt.	5560.00	222400.00
13	Demolition and desposal of unserviceable materials with all lead and lift. (II) Unreinforced cement concrete.	23.00	One Cum	637.85	14670.55

Item No.	Description of Item (With brief specification and reference to book of Specification)	Quantity	Unit	Rate	Amount
14	Earthwork for embankment including breaking clods, dressing with all lead and lift (Excluding watering and consolidation) (A) From borrow area with all lead and lift.Executed with machineries.(Selected soil to be used for earthwork shall be from BORROW AREA only having CBR not less than 6.00%)	442.00	One Cum	161.67	71458.14
15	Box cutting the road surface to proper slope and camber for making a base for road work including removing the excavated stuff and depositing on the road side slopes as directed upto all lead.	187.00	One Cum	112.01	20945.87
16	Supplying, stacking, spreading, rolling, watering and consolidation to desired density of quarry spall with all lead and lift.	157.00	One Cum	430.19	67539.83
17	WBM Grading-1 Providing, laying, spreading and compacting stone agg. Of 90mm to 45mm size to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 KN in stage to proper grade and camber, applying and brooming, stone screening/binding material to fill-up the intersties of coarse agg., watering and compacting to the required density grading-1 as per Technical Specification Clause.405 By manual means.	389.00	One Cum	1431.38	556806.82
18	Rolling and Watering of earthwork in layers with vibratory roller including filling in depression which occur during the process as directed.	383.00	One Cum	23.17	8874.11
19	Providing and Fixing Flood guage post confirming to IRC 67-2001 using engineering grade retro reflective sheeting including lettering and border as directed. For New structure.	8.00	One No	3046.16	24369.28

Item No.	Description of Item (With brief specification and reference to book of Specification)	Quantity	Unit	Rate	Amount
20	Informatory Signs :-Providing and fixing sing boards made out of 2mm aluminium sheet; size 80 x 60cms. rectangle as per the design of IRC-67-1977 pre treated with phospheting process & acid teching; coated with one coat of epoxyprimer and two coats of best qualityepoxy paint; reflectorised with retro reflective sheeting as per latest M.O.S.T. Specifications; 3.1m long stand postand frame fabricated from suitable sizeiron angle of 35 x 35 x 3mm75x75x6mm as required; painted with best qualityepoxy coatings in black and whitebends. the details of symbol for eachboard shall details of symbol for eachboard shall be as per the instruction ofengineer in charge. The fixing at site shall be in 1:2:4 CC block of size 45 x45 x 60cms. for each leg. including excavation curing tec. complete under the supervision of engineer in charge.(A) Engineer Grade(VR)...	2.00	One No	3856.89	7713.78
21	Hazard Marker sign : Providing and Fixing sign boards made out of 2mm aluminum sheet : size 90*30 cms. rectangle as per design / Drawing attached (IRC). Pretreated with phospheting process and acid etching : coated with one coat of epoxy primer and two coats of best quality epoxy paint: reflectorised with retro reflective sheeting as per latest M.O.S.T specification: 3.1 M. long (2 nos) stand post and frame fabricated from suitable size iron angle of 35*35*3mm and 50*50*5mm : painted with best quality epoxy coatings in black and white bends the details of symbole or inscription / numerals for each board shall be as per the instruction of engineer in charge the fixing at site shall be in 1:2:4 CC block of size 45*45*60 cms for each leg: including excvation curing etc. comp.under the supervision of engineer-in-charge.(B) Engineering Grade	4.00	One No	2423.73	9694.92

Item No.	Description of Item (With brief specification and reference to book of Specification)	Quantity	Unit	Rate	Amount
22	Cautionary Warning Sign : Providing and fixing sign boards made out of 2mm Aluminium sheet size 90x90x90 cms. Equilateral triangle as per the design of IRC-67-1977 pre treated with phospheting process and acid etching coated with one coat of apoxy primer and two coats of best quality epoxy paint reflectorised with retro reflective sheeting as per latest MOST specification 3.1 Mt. long stand post and frame fabricated from suitable size iron angle of 35x35x3mm, 75x75x6mm. as required painted with best quality epoxy coating in black and white bends the details of symbole for each board shall be as per the instruction of Engineer in charge the fixing at site shall be in 1:2:4 CC block of size 45x45x60cms. for each leg including excavation curring etc. complete under the supervision of engineer in charge (A) Engineering Grade.	6.00	One No	3808.65	22851.90
#NAME?					9989232.70

I \ We am \ are willing to carry out the work at % above \ bellow percent (Should be written in figures and words) of the estimated rate mentioned above. Amount of My \ Our tender works put as under.

* Estimated Amount

Put to tender **Rs**.....

Deduct.....%

Net **Rs**.....

In words.....

* Estimated Amount

Put to tender **Rs**.....

Add.....%

Total **Rs**.....

In words.....

1.The Contractor shall exhibit a board with detailed specification and details of work as directed by the Engineer-In-Charge for which no extra payment shall be made.

2.The labour cess will be deducted as per prevailing rules i.e. 1% of the work done.

3.GST and Income tax TDS will be deducted at a source while making payments of bills

4.In all R.C.C. Items in Rate Analysis Standard Cement Consumption has been taken as per Govt. G.R.: PRC-10/2017 Cement Consumption/16/C Date:11/05/2017 as stated in

S.O.R. therefore in R.C.C. items where there is a change as per actual mix design the cost of difference of cement consumption have been deducted from the rate of original item at the rate of input rate mentioned in all the tender.

Signature of Contractor.

Deputy Executive Engineer
Panchayat R&B Sub Division
Shihor

Executive Engineer
Panchayat R&B Division
Bhavnagar

Percentage Rate

Current Tender Details

Tender ID: 282008	Notice No.: 32/2025-26 of Bhavnagar Sr. No.1	Last Date For Bid Submission:: 16-03-2026 18:00:00
ECV: 9989232.70	Name of Work: Construction of New Structure of Bhavnagar District Package No.RPC-2/BVN/MMGSY/Normal/2025-26/P.02 Ta.Shihor , Dist.; Bhavnagar	Location: Bhavnagar
Open/WORKS	Client Name : Roads and Buildings	Sub Department : Bhavnagar Panchayat Division

Ra nk	Name of Party	Estimated Amount	Above /Below	Percentag e(%)	Total Amount	Amount in Words
L1	vivek construction (vivek_construction)	9989232.70	BELOW	27.33	7259175.40	Seventy Two Lacs Fifty Nine Thousand One Hundred Seventy Five Point Forty Only
L2	HARPALSINH AMARSINH SARVAIYA (harpalsingh)	9989232.70	BELOW	22.77	7714684.41	Seventy Seven Lacs Fourteen Thousand Six Hundred Eighty Four Point Forty One Only
L3	DEV CONSTRUCTION (dhgohil)	9989232.70	BELOW	22.52	7739657.50	Seventy Seven Lacs Thirty Nine Thousand Six Hundred Fifty Seven Point Fifty Only
L4	SWASTIK CONSTRUCTION (KULDEEP_12345)	9989232.70	BELOW	21.61	7830559.51	Seventy Eight Lacs Thirty Thousand Five Hundred Fifty Nine Point Fifty One Only
L5	GOHIL SURYADEEPSINH JAYDEVSINH (sjgohil19)	9989232.70	BELOW	15.22	8468871.48	Eighty Four Lacs Sixty Eight Thousand Eight Hundred Seventy One Point Forty Eight Only
L6	MAA BUILDCON (maabuildcon)	9989232.70	BELOW	14.40	8550783.19	Eighty Five Lacs Fifty Thousand Seven Hundred Eighty Three Point Nineteen Only
L7	MAHI INFRASTRUCTURE (hjmer1990)	9989232.70	BELOW	12.16	8774542.00	Eighty Seven Lacs Seventy Four Thousand Five Hundred Forty Two Only
L8	MOGAL CONSTRUCTION (mogalconst)	9989232.70	BELOW	10.55	8935368.65	Eighty Nine Lacs Thirty Five Thousand Three Hundred Sixty Eight Point Sixty Five Only
L9	Gajendrasinh V. Sarvaiya (gvsarvaiya)	9989232.70	BELOW	8.10	9180104.85	Ninety One Lacs Eighty Thousand One Hundred Four Point Eighty Five Only
L10	BRIJRAJ CONSTRUCTION (brijraj)	9989232.70	BELOW	7.75	9215067.17	Ninety Two Lacs Fifteen Thousand Sixty Seven Point Seventeen Only
L11	BHATA CONSTRUCTION (joshipi)	9989232.70	BELOW	6.66	9323949.80	Ninety Three Lacs Twenty Three Thousand Nine Hundred Forty Nine Point Eighty Only

L12	Bhagyalaxmi Construction (bgylaxmi)	9989232.70	BELOW	2.71	9718524.49	Ninety Seven Lacs Eighteen Thousand Five Hundred Twenty Four Point Forty Nine Only
-----	-------------------------------------	------------	-------	------	------------	---

As per tender documents.

Committee Members

Opening Committee	Decrypter	Alternate Decrypter	Evaluator
A.M.Jha (rnbbhvamj)	A.M.Jha (rnbbhvamj)	(N/A)	A.M.Jha (rnbbhvamj)